

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas


RECEIVED

SEP 21 1967

Form CP-4

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

GRAHAM County. Sec. 33 Twp. 9 Rge. 21 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines SW NE NW  
Lease Owner Ralph R. Rhyne  
Lease Name Cox Well No. 6 SWD  
Office Address Box 385, Russell, Kansas 67665  
Character of Well (completed as Oil, Gas or Dry Hole) SWD  
Date well completed 6-22 19 67  
Application for plugging filed 6-27 19 67  
Application for plugging approved 6-28 19 67  
Plugging commenced 9-7 19 67  
Plugging completed 2 PM 9-11 19 67  
Reason for abandonment of well or producing formation not needed

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols  
Producing formation Depth to top Bottom Total Depth of Well 4304 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	5 1/2			8 5/8	230	none
				5 1/2	3935	none
	SEP 25 1967					
	9/25/67					
	CONSERVATION DIVISION					
	Wichita, Kansas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded back from 4304' to 3850'.  
Dumped 5 sacks cement with dump bailer.  
Pushed plug to 1550', sanded back to 1490',  
dumped 5 sacks cement with dump bailer.  
Bailed hole dry, filled to cellar with 7 1/2 yds Ready-mix.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor  
Address

STATE OF RUSSELL KANSAS COUNTY OF RUSSELL, ss.  
RALPH R. RHYNE (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph R. Rhyne  
Box 385 Russell, Kas.  
(Address)

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of September, 1967

My commission expires September 27, 1971

Notary Public.

## WELL LOG

15-065-19003-00-07

OPERATOR: EL DORADO REFINING COMPANY  
Koch Building  
Wichita, Kansas

FARM NAME: #6 COX

LOCATION: SW NE NW  
33-98-21W  
Graham County, Kansas

CONTRACTOR: K & E DRILLING, INC.  
719 Union Center Building  
Wichita, Kansas

COMMENCE: 9-20-56  
COMPLETE: 9-29-56

CASING: 8-5/8" @ 230 (150 sx)

PRODUCTION: D & A

R.T.D. 3915'

## FORMATION RECORD

Depths shown indicate bottom of formation

Clay & Sand	65
Sand	95
Clay & Shale	110
Shale	750
Shale & Sand	1310
Sand	1540
Shale & Red Bed	1790
Anhydrite	1840
Shale & Shells	2190
Shale & Lime	2360
Lime & Shale	2635
Lime	3020
Lime & Shale	3560
Lime	3745
Lime & Shale	3895
Shale	3904
Arbuckle	3915
R.T.D.	3915'

## CERTIFICATE

STATE OF KANSAS )  
 ) SS:  
COUNTY OF SEDGWICK)

I hereby certify that the above information is true and correct to the best of my knowledge.

  
Dale Silcott

Subscribed and sworn to be fore me this 2nd day of October, 1956.

  
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

PLUGGING			
FILE	SEC	T	R
	33	9	21W
BOOK	PAGE	LINE	
	102	43	

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1957

CONSERVATION DIVISION  
Wichita, Kansas

15-065-19003-00-0/


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas

Company- EL DORADO REFINING COMPANY  
Farm- Cox No. 6

SEC. 33 T. 9 R. 21W  
SW NE NW

Total Depth. 3915'  
Comm. 9-20-56  
Shot or Treated.  
Contractor. K & E Drilling, Inc.  
Issued. 11-3-56

County Graham KANSAS



CASING:

8 5/8" @230' w/150 sx cem.

Elevation. 2325' DF

Production. Dry

Figures Indicate Bottom of Formations

clay & sand	65
sand	95
clay & shale	110
shale	750
shale & sand	1310
sand	1540
shale & red bed	1790
Anhydrite	1840
shale & shells	2190
lime & shale	2635
lime	3020
lime & shale	3560
lime	3745
lime & shale	3895
shale	3904
Arbuckle	3915 R.F.D.
Total Depth	

TOPS:	
Anhydrite	1790
Hoebner	3517
Toronto	3542
Lansing	3555
Base/Kansas City	3785
Conglomerate	3879
Arbuckle	3903

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 25 1957  
CONSERVATION DIVISION  
Wichita, Kansas