

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Cox Well No. B-1

Location NW-SW-NE Sec. 26 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3818'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #361, Great Bend, Kansas, License No. 399

Operation Completed: Hour 9:30 AM Day 15 Month 5 Year 1969

The above well was plugged as follows:

187'---8 5/8" Surface casing, cement circulated.

3816'---5 1/2" Production casing cemented on bottom with 100 Sx. Open hole completion.  
5 1/2" has been squeezed thru Dakota break-in.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well initially with 5 sacks hulls and 3 sacks gel and followed with 100  
Sx. cement from 900' to 575' then 9 sacks gel from 575' to 215' and followed with 20  
Sx. cement from 215' to 155' then 3 sacks gel from 155' to 30' and finally 10 Sx.  
cement from 30' to bottom of cellar. Maximum pump-in pressure-100#. Final shut-in  
Pressure---50#. Recovered 711' casing. (Mudding and cementing by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/16/69  
INV. NO. 9999-U

Signed: A. L. Dichel  
Well Plugging Supervisor