

Form CP-3  
Rev. 6-26-62KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, KansasRECEIVED  
STATE CORPORATION COMMISSION  
3/2/64  
MAR 2 1964CONSERVATION DIVISION  
Wichita, KansasOperator's Full Name Herman Geo. Kaiser, Oil Producer,Complete Address: 909 Palace Building, Tulsa, Oklahoma.Lease Name Bragg Well No. 4Location SW SE-NE Sec. 33 Twp. 9 Rge. (E) (W)21County Graham Total Depth 3880Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A Other well as hereafter indicated: Plugging Contractor: Southwest Casing Pulling Co., Inc.Address: Box #364, Great Bend, Kansas. License No. 399Operation Completed: Hour 4:00PM Day 25 Month 2 Year 1964

The Above well was plugged as follows:

223'--8 5/8" Surface pipe, cement circulated with 135 Sx. 3875'--5 1/2" pro-  
duction casing cemented with 125 Sx.Sanded well back to 3870' and set 5 Sx. cement with dump bailer. Pulled 5 1/2"  
to 575' and pumped in 16 Sx. gel, hole would not circulate. Pulled 5 1/2" to  
450' and pumped in 11 Sx. gel, hole still would not circulate. Pulled 5 1/2"  
to 280', mixed 3 Sx. gel hole circulated, displaced 45 Sx. cement thru 5 1/2"  
@ 280'. Pulled 5 1/2", set rock bridge @ 35' and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/2/64  
INV. NO. 8425-WSigned: W. L. Nichols  
Well Plugging Supervisor