

 KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
5/27/63
MAY 27 1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name American Petrofina Company of Texas,
Complete Address: Box #209, Russell, Kansas.
Lease Name Cox Well No. 2
Location SE-NE-NW Sec. 33 Twp. 9 Rge. (E) (W) 21
County Graham Total Depth 3886
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Knight Casing Pulling Company,
Address: Box #405, Chase, Kansas License No. 436
Operation Completed: Hour 9:00PM Day 20 Month 5 Year 1963

The Above well was plugged as follows:

198'--8 5/8" surface pipe, cement circulated with 135 Sx.

3875' 5 1/2", cemented with 75 Sx.

Sanded well back to 3865' and set 5 Sx cement with dump bailer.

Pulled 5 1/2" to 600', circulated heavy mud(21 Sx gel) and displaced 20 Sx

cement thru 5 1/2". Pulled casing to 200' and displaced 20 Sx cement thru

5 1/2". Pulled casing, set bridge and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/28/63
INV. NO. 1738-W

Signed: W. L. Nichols
Well Plugging Supervisor