

Form CP-3  
Rev. 6-26-62

*76*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

**RECEIVED**  
STATE CORPORATION COMMISSION  
5/27/63  
MAY 27 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name American Petrofina Company of Texas,

Complete Address: Box #209, Russell, Kansas.

Lease Name Cox Well No. 4

Location CNE-NW-NW Sec. 33 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 390.5

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 4:00PM Day 21 Month 5 Year 1963

The Above well was plugged as follows:

218'--8 5/8" Surface pipe, cement circulated with 150 Sacks.

3903'--5 1/2" cemented with 75 sacks. 5 1/2" squeezed @ 1292' with 200 Sx. cement,  
Sanded well back to 3900' and set 5 Sx cement with dump bailer.

Filled 5 1/2" from 1300' to 700' with heavy gel mud, shot pipe @ 692', pulled  
1 joint and displaced 20 Sx cement thru 5 1/2". Pulled casing, filled hole  
with heavy mud to 200', set bridge and 20 Sx cement. Heavy mud to 35', set  
bridge and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**  
DATE 5/28/63  
INV. NO. 9159-W

Signed: W. L. Dechels  
Well Plugging Supervisor