

*Ye*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION  
5/27/63  
MAY 27 1963

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name American Petrofina Company of Texas,

Complete Address: Box #209, Russell, Kansas.

Lease Name Cox # Well No. 5

Location NW-NW-NW Sec. 33 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3903

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company,

Address: Box #405, Chase, Kansas. License No. 436

Operation Completed: Hour 6:00PM Day 23 Month 5 Year 1963

The Above well was plugged as follows:

255'--8 5/8" surface pipe, cement circulated with 150 Sx.  
3900'--5 1/2" cemented with 75 Sx on bottom and 500 Sx thru DV tool @ 1600'.  
Temperature Survey showed top of cement on 5 1/2" @ 650'.

Pulled casing to 600' and circulated heavy gel mud and displaced 20 Sx  
cement thru 5 1/2". Pulled casing, bailed hole to 200', set rock bridge and  
20 Sx cement. Heavy mud to 35', set bridge and 10 Sx cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: W. L. T. Jochala  
Well Plugging Supervisor

DATE 5/28/63  
INV. NO. 7140-W