

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Ralph R. Rhyne,

Complete Address: Box #385, Russell, Kansas.

Lease Name Cox # Well No. 6 SWD

Location SW-NE-NW Sec. 33 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 4304'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 2:00PM Day 11 Month 9 Year 1967

The Above well was plugged as follows:

230'--8 5/8" Surface pipe, cement circulated with 150 Sx.

3935'--5 1/2" casing cemented with 200 Sx. on bottom. DV tool set @ 1790' with 400 Sx.

cement circulated.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pushed plug to 1550'

and sanded well back to 1490' and set 5 Sx. cement with dump bailer. Let cement set

bailed hole dry to plug and filled to cellar with Redi-Mix cement using 7 1/2 yards.

I hereby certify that the above well was plugged as herein stated.

INVOICED

SEP 15 1967

DATE

9/15/67

9/15/67

Signed:

A. L. Nichols

Well Plugging Supervisor

INV. NO.

6343-W

CONSERVATION DIVISION
Wichita, Kansas