

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 211 North Broadway
 Wichita, Kansas

FILE NO. _____

LOCATION NW NW SWSEC. 33 TWP. 9 RGE. 21

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease FrazierOperator Jones Shelburne Farmer Address Russell, KansField _____ County GrahamTotal Depth 3914 Feet.Plugging Contractor Forbes Casing Pulling CoPlugging Contractor's License No. 49

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 160' circulated with cement - 5 1/2" at 3905' with50 sax cement behind and squeezed with additional 50 sax at1833'.P.B. to 3910', perforated at 3904', filled with sand to 3890',set 4 sax cement with dump bailer, pulled 500' 5 1/2", filled withmud to 160', set rock and 15 sax cement, mud to 35', set rockand 10 sax cement to bottom cellar.

Edson Petty
 District Conservation Agent

Date 7-27-56

FILED
 COMMISSION
 7/31/56
 COMMISSION

PLUGGING
 FILE SEC. 33 T. 9 R. 21W
 BOOK PAGE 85 LINE 35