



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 4 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name C & G Drilling Company,

Complete Address 1107 Union National Bank Building, Wichita, Kansas.

Lease Name DeYoung Well No. 1

Location SW-SW-SW Sec. 35 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3834'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 10:00 AM Day 30 Month 10 Year 1974

The above well was plugged as follows:

234'--8 5/8" Surface casing, cement circulated with 150 Sx.
3831'--5 1/2" Production casing cemented on bottom with 100 Sx. (Open hole completion).

Sanded well back to 3815' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 5 sacks gel and 13 sacks gel followed with 110 Cu.
Ft. cement from 900' to 575' then 8 sacks gel from 575' to 255' and followed with
30 Cu. Ft. cement from 255' to 180' then 4 sacks gel from 180' to 20' and finally
10 Cu. Ft. cement from 20' to bottom of cellar. Maximum pump-in pressure-100#.
FSIP-50#. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 11/4/74
INV. NO. 232-W