

6-4

4-032241

22689-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-065-227008  
200' N. of SW NE NE / 4 SEC. 35, 09, 21 W  
4490 feet from S section line  
990 feet from E section line

Operator license# 4952

Lease: DeYoung Well # 4

Operator: Starr F. Schlobohm

County: Graham 124.54

Address: 47 Michawanic Road #3D  
Ossipee, N.H. 03864-3787

Well total depth 3832 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 1095 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 4 Month: June Year: 1997

Plugging proposal received from: John Driscoll

Company: Starr F. Schlobohm Phone: -

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

6/30/97

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: 11:00 A.M., Day: 4 Month: June, Year: 1997

Actual plugging report: 8 5/8" set at 1095' w/400 sxs cwc. 5 1/2" set at 3831' with 200 sxs. PBTD 3805'. Prod. Perf. 3729' - 3767'. Mixed and pumped down 5 1/2" w/50 sxs cement blend w/300# hulls mixed in followed with 13 sxs gel spacer, followed with 130 sxs cement blend with 100# hulls mixed in to Max. P.S.I. 1600#. Close in P.S.I. 1000#. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 500#. Close in P.S.I. 300#. Plug complete.

Remarks:       
Condition of casing(in hole): GOOD      BAD      Anhy.plug: YES X NO       
Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING     . Elevation:      GL

I did X / did not      observe the plugging.

Carl Goodrow  
(agent)

**INVOICED**  
DATE JUL 03 1997  
INV. NO. 48468

120