

M

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Century Oil Company,

Complete Address 925 O. W. Garvey Building, Wichita, Kansas.

Lease Name DeYoung Well No. 1

Location SW-NE-NE Sec. 35 Twp. 9 Rge. (E) (W) 21

County Graham Total Depth 3950'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kans. License No.

Operation Completed: Hour 3:00 AM Day 3 Month 12 Year 1971

The above well was plugged as follows:

168'--8 5/8" Surface casing, cement circulated with 140 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 100 Sx. cement thru
DP from 800' to 475'. Pulled DP to 180' and displaced 25 Sx. cement thru DP from
180' to 105'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/9/71
INV. NO. 4779-W

Signed: *A. L. Dinkel*
Well Plugging Supervisor