



Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

4/21/75  
APR 21 1975

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Assn.  
Complete Address Box 6 Great Bend, Kansas, 67530  
Lease Name Van Loenen Well No. #1  
Location NW-NW-NE Sec. 14 Twp. 9 Rge. 22 (E) (W)   
County Graham. Total Depth 3886'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor South West Casing Pulling Co. Inc.  
Address P.O. Box 364, Great Bend, Ks License No. 399  
Operation Completed: Hour 12:00 P.M. Day 16 Month April. Year 1975

The above well was plugged as follows:

KB. 2262' Dak Top. 1550' S.P. 142' of 8 5/8" cwc. 125 sx cem.  
4 1/2" Casing 3835' set w/ 125 sx cem. Plug Back 3803  
Perf. 3652 - 58- Bottom Plug set @ 3600' w/ sand & 43x cem.  
Pumped down 8 5/8- 5 sx Hulls, 21 sx Gel 70 sx cem  
50/50 Pozmix 6% Gel, 9 Gel, Plug, 455 sx cem 50/50  
Pozmix. 6% Gel. Max Pressure 300 lbs.  
Allied Cementing.  
Recovered 18 lbs 540' of 4 1/2" Casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 4/22/75  
INV. NO. 1201-W

Signed: Gullert Balthasar  
Well Plugging Supervisor