

KANSAS

Form CP-3
Rev. 6-4-68

**STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED
STATE CORPORATION COMMISSION
12/2/74
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association,

Complete Address P. O. Box #6, Great Bend, Kansas.

Lease Name Van Loenen Well No. 3

Location SW-SW-NE Sec. 14 Twp. 9 Rge. (E) (W) 22

County Graham Total Depth 3837'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address P. O. Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 12:30 PM Day 29 Month 11 Year 1974

The above well was plugged as follows:

195'--8 5/8" Surface casing, cement circulated.
3836'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3740'. Top perforations from 3534' to 3542'.
Sanded well back to 3500' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (1275') and squeezed well initially with 5 sacks hulls and 12 sacks gel following with 110 Cu. Ft. cement from 950' to 625' then 10 sacks gel from 625' to 225' and followed with 30 Cu. Ft. cement from 225' to 150' then 3 sacks gel from 150' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure-300%. Final Shut-in pressure-100%. Mudding and cementing by Allied Cementing Co., Inc.,).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 12/4/74

INV. NO. 393W