

R 15-163-03628-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

5/27/60  
STATE CORPORATION COMMISSION  
MAY 27 1960  
CONSERVATION DIVISION  
Wichita, Kansas

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: Ellis

Location: SW SW NW Sec. 16 Twp. 9 Rge. 16 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3390

I have this date completed supervision of plugging of:

Lease Name: Finnesy Well No. 1

Operator's Full Name: Morganstern - Specter

Complete Address: Box 661 Russell, Kans

Plugging Contractor: E & L Pipe Pulling Co

Address: Great Bend, Kans License No. 377

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 7PM Day 24 Month 5 Year 60

The above well was plugged as follows:

8 5/8" 206' circulated with cement - 5 1/2" <sup>3387</sup> 3389' with 100 sax cement.

Filled with sand to 3320', set 4 sax cement with dump bailer, pulled

2400' 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550',

Ø 31 sax (el), displaced 15 sax cement through 5 1/2" at 550', heavy mud to

170', displaced 15 sax cement through 5 1/2" at 170', heavy mud to 25', set

bridge and filled to bottom cellar with cement.

Mudding and cementing by E & L Co pump truck.

Signed: [Signature]  
Conservation Division Agent

Reviewed: [Signature]  
Field Supervisor

Remarks:

INVOICED  
DATE 6/2/60  
INV. NO. 1446-w