

15-163-20476-00-00

KANSAS

Form CP-3
Rev. 6-4-68

JLP
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
FEB 9 1973
CONSERVATION DIVISION
Wichita, Kansas
2/9/73

Operator's Full Name Clinton Oil Company
Complete Address 217 N. Water Wichita, Kansas
Lease Name James Casey Well No. 1-V
Location NE SW SW Sec. 15 Twp. 9 Rge. (E) (W) 16
County Rooks ~~XX~~ Total Depth 3690'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Red Tiger Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 10 A Day 7 Month 2 Year 1973

The above well was plugged as follows:

RTD 3690' 10 3/4 csg set at 240' cwc 200 sk Cmt. Mat. 50-50 poz cmt W/6% gel.
Drilled 9" hole to Anhydrite.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 80 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 15 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo L. Messer
Well Plugging Supervisor

INDEXED
DATE 6967-W
INV. NO. 67 2/12/73