

KANSAS

15-163-~~0360~~-0000

STATE CORPORATION COMMISSION

03606

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1974

CONSERVATION DIVISION
Wichita, Kansas

2/19/74

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Cities Service Oil Company

Complete Address 700 Sutton Place, Wichita, Kansas 67202

Lease Name Deer Unit Well No. 503

Location C NE NW SW Sec. 16 Twp. 9 Rge. (E) (W) 16

County Reeks Total Depth 3373'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Co. Teels by HOWCO

Address License No.

Operation Completed: Hour 1:30 P Day 15 Month 2 Year 1974

The above well was plugged as follows:

Total Depth 3373' 8 5/8 esg set at 250' cwe 150 sk.

5 1/2 esg set at 3372' cw 250 sk cem.

5 1/2 esg PBTD 3351' with perf. (3342'-3352')

5 1/2 esg squeezed at 858'-895' -& 908' W/206 sk cem. at 1500 # pres. No pipe recovered.

Pumped down 5 1/2 esg with 25 sk cem. -30 sk gel & water W/200 lbs hulls -released 5 1/2 plug and pumped 60 sk cement. PP 700 lbs. SIP 500 lbs.

Pumped down annulus to 400 lbs with 15 sk cem.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/20/74

INV. NO. 8603-4