

15-163-03608-00-00  
DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 56-25

LOCATION Sw-Sw-Nw

SEC. 16 TWP. 9 RGE. 16W

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Finnesy R.J. Finnesy <sup>KCC</sup> <sub>2147</sub>

Operator Louis Mai Address Russell Kans.

Field \_\_\_\_\_ County Rooks

Total Depth 3372 Feet.

Plugging Contractor Jayhawk Casing Pulling Co.

Plugging Contractor's License No. 19

Address Russell Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 13" @ 154' CWC 8 3/4" @ 1263' w/400 H Cem.  
5 1/2" set 3372' w/ 150 H Cem. Cement back to  
3362' Perf 3136' Sand to 3120 dump 5 H Cem.  
Shot off and pulled 5 1/2" casing. Mud to 225  
H. bridge and 20 H Cem. Mud to 35'  
H. bridge and 10 H Cem to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1954

CONSERVATION DIVISION  
Wichita, Kansas

Warren H. Horner  
District Conservation Agent

Date Aug 17, 1954

*8/15/54*

PLUGGING  
FILE SEC 10 T 9 R 16W  
BOOK PAGE 56 LINE 25