

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 142-4

LOCATION SE-SE-SE

SEC. 18 TWP. 9 RGE. 16-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Bell

Operator Cities Service Oil Co Address Box 751 - Great Bend - Kas

Field _____ County Rooks

Total Depth 3470 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 236 ft - Circulated with Cement
5 1/2" casing Set at 3470 ft cemented with 150 sacks of
Cement - Hans Wells Plug set at 3390 ft - 5 1/2" casing
Separated & well tested - No Oil - Filled hole back from
3390 ft to 3115 ft with sand - Put in 5 sacks of cement
with Mump Barley at 3115 ft - Shot off & recovered 2000 ft
of 5 1/2" casing - filled with mud to 235 ft - Plug & 15 sacks
of Cement at 235 ft - Mud to 30 ft from the surface - Plug
& 10 sacks cement

C. M. Stough
District Conservation Agent

Patterson & Son

NOV 24 1947

Date 11-28-47

Pipe Pullers & Pluggers

PLUGGING
FILE SEC 18 T 9 R 16W
BOOK PAGE 142 LINE 4

11/24/47