

15-163-19040-00-01

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1968
CONSERVATION DIVISION
Wichita, Kansas
1/15/68

Operator's Full Name George P. Crawford

Complete Address Route 1 P. O. Box 93 Natoma, Kansas

Lease Name W. H. Hrabe Well No. 3

Location SE NW SE Sec. 1 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 1275

Abandoned Oil Well Gas Well Input Well SWD Well D & A X ^{SWD}

Other well as hereafter indicated Washdown

Plugging Contractor L. J. Dreiling & Sons, Inc.

Address Victoria, Kansas License No.

Operation Completed: Hour 1 P Day 12 Month 1 Year 1968

The above well was plugged as follows:

RTD 1275' 8 5/8 csg set at 193' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 540' and displaced 100 sc cem. thru drill pipe. Heavy mud to 180' set cementing plug and displaced 25 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: R. F. Massey
Well Plugging Supervisor

INVOICED

DATE 1/15/68
INV. NO. 7079-W