

15-163-03618-00-00

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 18 1960  
CONSERVATION DIVISION  
Wichita, Kansas

10/18/60

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: CE 1/2 NE NW Sec. 18 Twp. 9 Rgs. 16 (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3438

I have this date completed supervision of plugging of:

Lease Name: ~~V. E. Sheffer~~ Colonan Colahan <sup>KCC</sup> ~~CHP~~ Well No. 1

Operator's Full Name: V. E. Sheffer

Complete Address: Box 653 Russell, Kans

Plugging Contractor: C. E. Shull

Address: Great Bend, Kans License No. 8

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 12 Month 10 Year 60

The above well was plugged as follows:

10 3/4" 213' circulated with cement - 5 1/2" 3350' with 125 sax cement.  
Filled with sand to 3300', set 4 sax cement with dump bailer, pulled  
1700', 5 1/2" to 550', circulated hole with heavy mud through 5 1/2" at 550'  
(70 sax Gel), displaced 20 sax cement through 5 1/2" at 550', heavy mud to  
190', displaced 20 sax cement through 5 1/2" at 190', heavy mud to 30', set  
plug and 10 sax cement to bottom cellar.  
Mudding and cementing by Halliburton Cementing Co.

Signed: Eaton Peety  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED  
DATE 10/26/60  
INV. NO. 2052-W