

15-163-19213-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE SW NW

SEC. 18 TWP. 9 RGE. 16 W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Collahan~~ Colahan

Operator Don T. Ingling Address Wichita, Kans

Field Westhusin County Rooks

Total Depth 555 Feet.

(Describe briefly the manner in which the well was plugged)

10" at 77' circulated with cement - 3 1/2" at 5197.

Lane Wells plugs to 5145 - 3 1/2" squeezed at 890', with

100 sax - perforated above and squeezed with 25 sax at 1000'

Pumped hole full of mud, pushed plug to 400', with 15 sax

cement on top, followed by mud to 55', cement from 55' to

surface. Mudding and cementing by Sun Cementing Co.

District Conservation Agent

Date 11-8-49

PLUGGING
FILE SEC. 1879 R. (lat)
BOOK PAGE 123 LINE 34

11/10/49

RECEIVED
NOV 10 1949
DISTRICT CONSERVATION AGENT