

4

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20235-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 1 1969
CONSERVATION DIVISION
Wichita, Kansas

8-1-69

Operator's Full Name G & L Oil Co., Inc.

Complete Address 207 Petroleum Building Wichita, Kansas

Lease Name Hachmeister Well No. 1

Location SE NW NW Sec. 19 Twp. 9 Rge. (E) (W) 16

County Rooks Total Depth 3535

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 3:45A Day 29 Month 7 Year 1969

The above well was plugged as follows:

RTD 3535' 8 5/8 csg set at 190' cwc 150 sk Gmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/1/69

INV. NO. 216-W

Signed: Leo F. Marny
Well Plugging Supervisor