

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
JUN 10 1977
CONSERVATION DIVISION
WICHITA, KANSAS
6/10/77

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15-163-20678-00-00 (of this well)

Operator's Full Name Pickrell Drilling Company
Complete Address 205 Litwin Bldg., Wichita, Kansas 67202
Lease Name Twin Mounds Unit "D" Well No. 5
Location SE SW SE Sec. 4 Twp. 9 Rge. (E) (W) 17
County Rooks Total Depth 3520'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas 67526 License No. 462
Operation Completed: Hour 10:30 A Day 9 Month 6 Year 1977

The above well was plugged as follows:

Total Depth 3520' 8 5/8 csg set 239' cwc 150 sk.
4 1/2 csg set 3518' cw 125 sk cmt.
4 1/2 csg PBSD 3483' with perf. (3472 1/2)
Filled 4 1/2 csg W/sd (3483'-3450') dumped 3 sk cmt W/dump bailer (3450'-3420')
Cutoff & recovered 2536' of 4 1/2 csg.
Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs
hulls -followed with 50 sk 50-50 poz 6% -displaced with 5 sk gel & water & capped
with plug & 50 sk 50-50 poz 6% & shutin. FPP 350 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 6-10-77
INV. NO. 5303-W