

15-163-20037 - 00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

7/24/67

JUL 24 1967

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bank Building Wichita, Kansas

Lease Name Hrabe "B" Well No. 2

Location SW SE NE Sec. 3 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 3515

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co Tools Globe Cementing Co.

Address: Plainville, Kansas License No.

Operation Completed: Hour HA Day 23 Month 7 Year 1967

The Above well was plugged as follows:

RTD 8 5/8 csg set at 217' cwc 140 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 90 sc cem.

thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base

Of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/24/67
INV. NO. 6014-U

Signed: Leo F. M... ..
Well Plugging Supervisor