

15-163-20042-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
8/5/70 AUG 5 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address 705 4th Nat'l Bk. Bldg., Wichita, Kansas 67202

Lease Name Hrabe "B" Well No. 3

Location SW SE NW Sec. 3 Twp. 9 Rge. (E) (W) 17

County Rooks Total Depth 3507

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling

Address Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 10:30 A Day 4 Month 8 Year 1970

The above well was plugged as follows:

Total Depth 3507' 8 5/8 csg set at 204' cwo

1/2 csg set at 3505' (cw 160 sk cmt.)

1/2 csg perf. (3407-3410)

Set 1/2 wood plug 3350 -poured sd (3340-3350) Dumped 5 sk cmt W/dump bailer. (3300-3340)

Pumped thru 8 5/8 plug container with 15 sk gel W/300 lbs hulls -70 sk reg poz 6% -

5 sk gel -plug and 50 sk reg poz 6%.

Cmt (0-220) gel (220-420) Cmt (420-620) Gel & Hulls (620-TD)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lo F. Manning
Well Plugging Supervisor

DATE 8/6/70
INV. NO. 2339-W