

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-163-20135-00-00

Operator's Full Name Leo J. Breiling Oil Company

Complete Address: Victoria, Kansas

Lease Name Hrabe Well No. 1

Location NE SE NW NE Sec. 3 Twp. 9 Rge. 17 (E) (W) X

County Rooks Total Depth 3467

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 12N Day 11 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3467' 8 5/8 csg set at 163' cwc Cmt Mat 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sc cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

RECEIVED
STATE CORPORATION COMMISSION

Signed: Leo T. Wasey
Well Plugging Supervisor

DATE 10/14/68

OCT 14 1968

INV. NO. 8638-W

CONSERVATION DIVISION
Wichita, Kansas

10/14/68