

15-163-01036-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 11 TWP. 9 RGE. 16 W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Tatkenhorst

Operator Harold Krueger Address Natoma, Kans

Field Laton County Rooks

Total Depth 3375 Feet.

(Describe briefly the manner in which the well was plugged)

7" at 2965' - 5 1/2" 3262' - 12 1/2" from 200 to 800'

Filled with chat to 3250' set 4 sax cement with dump bailer,
pulled 2500' 5 1/2" and 2250' 7", filled hole with mud to 200',
set rock bridge and 20 sax cement, mud to 35', rock and 15 sax
cement to bottom cellar.

FEB 9 X 1952

2/9/52

[Signature]
District Conservation Agent

Date 2-4-52

PLUGGING
FILE SEC 11 T 9 R 16 W
BOOK PAGE 143 LINE 24