

15-143-03747-0000

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION CW $\frac{1}{2}$ NW NE

SEC. 11 TWP. 9 RGE. 16

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. C-1 Lease Livingood Broadview Hotel

Operator Broadview Oil Co. Address Emporia, Kans

Field Laton County Rooks

Total Depth 3310 Feet.

(Describe briefly the manner in which the well was plugged)

5 $\frac{1}{2}$ " at 3244' with 100 sax cement behind.

Chat to 3235', set 4 sax cement with dump bailer, pulled approx

1000' 5 $\frac{1}{2}$ ", filled hole with mud to 250', set rock bridge and 15

sax cement, mud to 25', set rock and 10 sax cement to bottom cellaar

RECEIVED
CORPORATION COMMISSION

JUL 31 1952

CONSERVATION DIVISION
Wichita, Kansas

Edson
District Conservation Agent

Date 7-29-52

PLUGGING
FILE SEC 11 TWP 9 RGE 16
BOOK PAGE 34 LINE 6

7/31/52
F