

15-163-00520-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 9 TWP. 9 RGE. 16 W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Finnesy

Operator Lee Phillips Oil Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 2800 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 170' circulated with cement. 5 1/2" at 2800' with 75 sax
cement behind - cement to 2700' - perforations at 2671'.

Filled with chat to 2650', set 4 sax cement with dump bailer,

pulled 2411' 5 1/2", filled hole with mud to 170', set rock and 15

sax cement, mud to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 9 T 9 R 16 W
BOOK PAGE 86 LINE 111

Edon Peely
District Conservation Agent
Date 3-20-56

3-23-53