


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____
LOCATION CS 1/2 SW SE
SEC. 10 TWP. 9 RGE. 16W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. \$ B-4 Lease Tatkenhorst
Operator Harold Krueger Address Natoma, Kans
Field Laton County Rooks
Total Depth 3330 Feet.

(Describe briefly the manner in which the well was plugged)

5 1/2" at 3240' with 75 sax cement behind.
Lane Wells plugs to 3220' - perforations at 2960'.
Filled with sand to 2950', set 4 sax cement with dump bailer,
pulled 1600' 5 1/2", filled with mud to 200', set rock and 20 sax
cement, filled with mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
2-1-1952
FEB 1 X 1952
CONSERVATION DIVISION
WICHITA, KANSAS

[Signature]
District Conservation Agent
Date 1-27-52

PLUGGING
FILE SEC. 10 T. 9 R. 16W
BOOK PAGE 148 LINE 7