

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 148-5

LOCATION C.W.F. ^{SE} 27-7E

SEC. 10 TWP. 9 RGE. 16.W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Beardmore

Operator Cash Refining Corp Address 402 Schwartz Bldg - Wichita - Kans.

Field _____ County Rooks

Total Depth 3218 Feet.

(Describe briefly the manner in which the well was plugged)

No Surface Pipe left in hole - Drilled with Cable Tools
The 5" casing set at 3163ft & cemented - Filled
hole back from bottom to 3160ft with sand - Put in
7 1/2 sacks of cement at 3160ft - with Mumps Bailey
Shot off & recovered 5" casing - Filled with Mud to
200ft - Plug & 16 sacks cement at 200ft - Mud to
within 20ft of the surface - Plug & 16 sacks cement.

Mr. Betsy - Pipe Puller
& Plugger

C. M. Stough
District Conservation Agent

Date 1-16-48 20-1948

PLUGGING
FILE SEC 10 T 9 R 16W
BOOK PAGE 148 LINE 5