

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-163-20390-00-00

RECEIVED
STATE CORPORATION COMMISSION
SEP 2 1971
CONSERVATION DIVISION
Wichita, Kansas

9-2-71

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Black Petroleum, Inc.
Complete Address 445 O. W. Garvey Bldg., Wichita, Kansas
Lease Name Becker Well No. 1
Location SW SW SE Sec. 27 Twp. 9 Rge. (E) (W) 16
County Rooks Total Depth 3625
Abandoned Oil Well XX A Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor Shields Drlg.
Address Russell, Kansas License No.
Operation Completed: Hour 11:30 P Day 31 Month 8 Year 1971

The above well was plugged as follows:

RTD 3625' 8 5/8 csg set at 224' cwc cmt. Mat. 50-50 poz W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9-2-71

INV. NO. 4273-W

Signed: Leo F. Massey
Well Plugging Supervisor