

API NUMBER 15-065-20,105 -00-01

LEASE NAME Brandyberry ~~OWHO~~

WELL NUMBER 1 KCC ZAP

 Ft. from S Section Line

NW SW Ft. from E Section Line

SEC. 17 TWP. 9S RGE. 22W (E) or (W)

COUNTY Graham

Date Well Completed

Plugging Commenced 10-24-94

Plugging Completed 10-24-94

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Berexco, Inc.

ADDRESS Box 723 Hays, Kansas 67601

PHONE# (913) 628 6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-24-94 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3716

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	228	8 5/8		
	Casing	0	3703	5 1/2		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perf. 2 holes at 2380' and 1950'. 3180.43 spot 75 sk. 60/40 pos. 10% gel. 200# hulls 2080.36 spot 75 sk. 60/40 pos. 10% gel 100# hulls 981 20 spot 50 sk. 60/40 pos. 10% gel 200# hulls no circulation 490.00 mix 50 sk. 60/40 pos. 10% gel. Circulate to surface. hook to 8 5/8 mix 50 sk. 60/40 pos. 10% gel. Max. 50#. Shut in 50#. Top off 5' with 25 sk. 60/40 pos. 10% gel.

Name of Plugging Contractor Berexco, Inc. License No. 5363

Address Box 723 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Ellis, ss.


Mr. Ted Crawford

(Employee of Operator or Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Mo. 67601



SUBSCRIBED AND SWORN TO before me this 20 day of January, 19 95

Rosemary Dineth
 Notary Public

5-1-1995

My Commission Expires:
USE ONLY ONE SIDE OF EACH FORM