

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 23 Twp. 9S Rge. 22 (W) (W)

Location as "NE/CNW&SW" or footage from lines NE-NW-SW

Lease Owner Aspen Drilling Co.

Lease Name Germany Well No. 1

Office Address P. O. Box 783 Great Bend, Kansas 67530

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed January 13 19 75

Application for plugging filed January 13 19 75

Application for plugging approved January 15 19 75


Plugging commenced January 13 19 75

Plugging completed January 13 19 75

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Dale Balthazor

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3908 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		- 0 -	279'	8 5/8"	279'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud to 950 ft. Plug set at 950 ft. with 70 sacks of 50-50 Pozmix
6% gel. Mud to 280 ft. Plug set at 280 ft. - mud to 40 ft. Plug
set at 40 ft. with 10 sacks common cement.

RECEIVED
STATE CORPORATION COMMISSION
1/24/75
1975

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Helberg Oil Company

Address Morland, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William S. Schackle

P. O. Box 783 Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 19 75

My commission expires June 17, 1976

Dorothy King
Notary Public.

15-065-20708-00-00

RECEIVED
STATE CORPORATION COMMISSION

JAN 29 1975

DRILLERS WELL LOG

CONSERVATION DIVISION
Wichita, Kansas

Date Commenced: December 30, 1974
Date Completed: January 13, 1975

Aspen Drilling Co.
GERMANY #1
NE-NW-SW Sec. 23 T9S-R22W
Graham County, Kansas

Sand	60'
Shale	870'
Sand	1000'
Shale	1035'
Shale & Sand	1575'
Shale & Shells	1809'
Anhydrite	1849'
Shale & Shells	2277'
Shale	2370'
Lime & Shale	3380'
Lime	3438'
Lime & Shale	3504'
Lime	3908'

Elevation: 2325 K.B.	
ELECTRIC LOG TOPS	
Anhydrite	1810
Heebner	3524
Lansing	3562
B/KC	3780
Marmaton	3802
Ft. Scott	3847
Conglomerate	3874
R. T. D.	3908

Surface Casing: Set used 8 5/8" surface casing at 279 ft. w/150 sacks common cement 3% calcium chloride.

Plugged: D & A
Plug at 950' w/70 sacks 50-50 pozmix 6% gel.
Plug at 280' - Plug at 40' w/10 sacks common cement.

STATE OF KANSAS)
) S.S.
COUNTY OF BARTON)

William S. Schachle of lawful age, does hereby swear and state that the facts and statements contained herein are true and correct to the best of his knowledge.

William S. Schachle
William S. Schachle

Subscribed and sworn to before me this 28th day of January, 1975.

My commission expires June 17, 1976

Dorothy King
Dorothy King - Notary Public