


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 24 Twp. 9S Rge. 22 ~~X~~/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
SE SW SE
Lease Owner T.G.T. Petroleum Corporation
Lease Name KERN Well No. 1
Office Address 209 East William, Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____
Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 07-02 1980
Application for plugging filed 07-02 1980
Application for plugging approved 07-02 1980
Plugging commenced 07-02 1980
Plugging completed 07-02 1980

Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3995'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

T.D. 3995'
Set 1st plug at 970' with 60 sx.
Set 2nd plug at 210' with 30 sx.
Set 3rd plug at 40' solid bridge with 10 sx.
Rathole with 5 sx. 50/50 posmix, 6% gel.

Plug was down at 1:15 a.m. 07-02-80.

RECEIVED
STATE CORPORATION COMMISSION
7/14/80
JUL 14 1980
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedwick, ss.
Jack L. Partridge, Asst. Sec.-Treas. (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature)

801 Union Center, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of July, 1980



My commission expires _____

Sherrie L. Brooks
Notary Public.

CONTRACTOR'S WELL LOG

OPERATOR: T.G.T. Petroleum Corporation
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: KERN #1
 LOCATION: SE SW SE, Section 24-9S-22W
 Graham County, Kansas
 SPUD DATE: 06-27-80
 COMPLETION DATE: 07-02-80

0	223	Top Soil, Sand & Shale
223	697	Shale
697	1888	Shale & Sand
1888	1925	Anhydrite
1925	2815	Shale
2815	3572	Lime & Shale
3572	3930	Lime
3930	3995	Lime & Chert
	3995	Rotary Total Depth

Spud at 8:45 p.m. 06-26-80. Drilled 223' in 12-14" hole. Ran 5 joints of 8-5/8" used 28# casing (tally 213.13) Set at 222'. Cemented with 165 sacks of common cement, 2% gel, 3% c.c. Cement did circulate. Plug was down at 1:15 a.m. on 06-27-80.

T.D. 3995'. Set 1st plug at 970' with 60 sx., set 2nd plug at 210' with 30 sx., set 3rd plug at 40' solid bridge with 10 sx., rathole with 5 sx., 50/50 posmix, 6% gel. State plugger was Marion Schmidt. Plug was down at 1:15 a.m. 07-02-80.

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

JUL 14 1980
 CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the KERN #1, SE SW SE, Section 24-9S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 9th day of July, 1980.

 **SHERRIE L. BROOKS**
 Sedgwick County, Ks.
 My Appt. Exp. 7-27-82

Sherrie L. Brooks
 Sherrie L. Brooks, Notary Public