

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 24 TWP. 9S RGE. 22W ~~EW~~
Location as in quarters or footage from lines:
NE SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner Chief Drilling Co., Inc.
Lease Name Kern Well No. #1
Office Address 905 Century Plaza Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
Date Well Completed 10-15-82
Application for plugging filed 10-15-82
Plugging commenced 10-15-82
Plugging completed 10-15-82
Reason for abandonment of well or producing formation dry hole

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt
Producing formation _____ Depth to top _____ bottom _____ T.D. 3906'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface Casing	8 5/8	210'	set @	213' cem.	w/150 sx.	

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged w/200 sx. 50-50 pos mix, 6% gel.
3% c.c., plug @ 3720' w/20 sx. plug @ 1860'
w/20 sx. plug @ 1080' w/100 sx., 40 sx., @
240', 10 sx., @ 40' - 0' 10 sx. in rathole,
200 sx., total, Started @ 9:30 p.m. Completed
@ 12:00 a.m.

RECEIVED
STATE CORPORATION COMMISSION
10/26/82
OCT 26 1982
CONSERVATION DIVISION
Wichita Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Warrior Drilling Company Rig #1

STATE OF Kansas COUNTY OF Graham, ss.
F.W. Shelton, Jr., (employee of ~~xxxx~~) ~~xxxx~~ (operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) F.W. Shelton, Jr.
F.W. Shelton, Jr., Vice Pred.
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 19 82

MARTHA E. GUSTIN
NOTARY PUBLIC
STATE OF KANSAS
My Commission expires 4-15-85

Martha E. Gustin
Notary Public.
Martha E. Gustin