


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

15-065-02198-00-00

NORTH



Locate well correctly on above  
Section Plat

Graham County, Sec. 24 Twp. 9S Rge. 22 (W)  
Location as "NE/CNW/SW" or footage from lines NE NE SE  
Lease Owner Sterling Drilling Company  
Lease Name Kern Well No. 1  
Office Address Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 1 19 58  
Application for plugging filed February 1 19 58  
Application for plugging approved February 1 19 58  
Plugging commenced February 1 19 58  
Plugging completed February 1 19 58  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius  
Producing formation Depth to top Bottom Total Depth of Well 3917 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	200'	8-5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Circulated. Set bottom plug @ 700' with 20 sacks cement. Set plug @ 170' with 15 sacks cement. Set top plug @ 40' with 10 sacks cement, 1/2 sack hulls.

STATE CORP. COM. FILED  
2/18/58  
CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company  
Address Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this day of 19

My commission expires My Commission Expires Jan. 22, 1962

Bernard Lauderbach Notary Public.

PLUGGING  
FILED 02 24 19 58 R. 22 W  
BOOK PAGE 80 LINE 38

STERLING DRILLING COMPANY  
Sterling, Kansas

WELL LOG ----- KERN #1  
Located: NE NE SE, Section 24-9S-22W, Graham County, Kansas

OWNER: Sterling Drilling Company  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: 1-24-58  
COMPLETED: 2-1-58

TOTAL DEPTH: 3947'

LOG

0 - 80	Clay & Sand
80 - 860	Shale
860 - 1585	Sand & Shale
1585 - 1855	Shale
1855 - 1890	Anhydrite
1890 - 1965	Red Bed
1965 - 2150	Red Bed & Shale
2150 - 2565	Lime & Shale
2565 - 2700	Lime
2700 - 3480	Shale & Lime
3480 - 3795	Lime
3795 - 3855	Lime & Shale
3855 - 3910	Lime & Conglomerate
3910 - 3947	Arbuckle T. D.

CASING RECORD

Set 8-5/8" surface casing @ 200'  
with 150 sacks cement, 2% c.c.

PRODUCTION RECORD

Plugged & Abandoned

**PLUGGING**  
 WELL NO. 24 E 9 R22W  
 BOOK PAGE 80 LINE 38

RECEIVED  
 COMMISSION  
 FEB 6 1958  
 OIL DIVISION  
 Kansas