

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-02992-00-00

API NUMBER _____

LEASE NAME Holzhauser "B"

WELL NUMBER #6 (406)

SPOT LOCATION SE NE NE

SEC. 26 TWP. 9 RGE. 22 (E or W)

COUNTY Graham

Date Well Completed 3-2-55

Plugging Commenced 4-19-84

Plugging Completed 4-19-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Collins & Collins Oil Company

ADDRESS 1007 Cody - Suite A, Hays, Kansas 67601

PHONE # (913) 628-1046 OPERATORS LICENSE NO. 8722

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? ? If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3811

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	250'	-0-
				5 1/2"	3811'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

filled hole with cement as per attached Allied invoice

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John B. Collins License No. 5465
Address 1007 Cody - Suite A, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Ellis, ss.

John B. Collins (operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John B. Collins
(Address) 1007 Cody - Suite A, Hays, KS

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 84

GLORIA J. BROWN
NOTARY PUBLIC
STATE OF KANSAS
My Commission Expires 7-15-84

Gloria Brown
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
5/15/84
MAY 15 1984
CONSERVATION DIVISION
Wichita, Kansas

WELL RECORD

15-065-02992-00-00

#406 W

Company Cities Service Oil Co. Well No. 6 Farm Holshauer "B"
 Location 990' South and 330' West of NE Cor. Sec. 26 T. 9 R. 22N
 Elevation 2366 (2363 Gr.) County Graham State Kansas
 Drlg. Comm. February 21, 1955 Contractor Lohmann-Johnson Drilling Co., Inc.
 Drlg. Comp. March 2, 1955 Acid 2000 gals. (3-8-55)
 T.D. 3811' Initial Prod. Physical Potential: 84 oil, 0.4% B. S. and water, 24 hrs
 P.B.T.D. 3764' (3-31-55)

CASING RECORD:
 8-5/8" @ 250' con. 175 sac cement
 5-1/2" @ 3811' con. 150 sac cement

FORMATION RECORD:

sand & shale	0-250
shale, sand & shells	1127
sand & shale	1255
shale & lime	1295
sand & shale	1360
sand	1550
shale	1860
anhydrite	1895
shale	2024
sand & shale	2280
shale & lime	2655
lime & shale	3120
shale	3399
shale & lime	3452
lime & shale	3810

3810 RTD = 3811 SIM

Corr. Topeka	3386'
Corr. Heebner	3543'
Corr. Dodge	3566'
Corr. Lansing	3580'
Corr. Base Kansas City	3799'
Corr. Total Depth	3811'

Drilled cement to 3764' S. L. M.

Perf. 37 shots 3720-29
 Perf. 44 shots 3618-29

3-8-55 Acidized 750 gals. 3720-29
 Acidized 1250 gals. 3618-29

SYFO:

500'	1°
1000'	1°
1500'	1°
2000'	0°
2500'	0°
3000'	1°

7-7/8" rotary hole.

SE NE NW