


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham County. Sec. 26 Twp. 9 Rge. (E) 22 (W)
Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW NE NW
Lease Owner Cities Service Oil
Lease Name Barber B Well No. 2
Office Address Bartlesville, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 1-11 19 51
Application for plugging filed 1-12 19 51
Application for plugging approved 1-12 19 51
Plugging commenced 1-12 19 51
Plugging completed 1-12 19 51
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Kansas City Depth to top 3559 Bottom Total Depth of Well 3963 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Kansas City	Dry			8 5/8	240'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 230-set plug and 15 sacks cement.
Heavy mud to 40'-plug and 10 sacks cement to
surface

RECEIVED
STATE CORPORATION COMMISSION
1/30/51
JAN 30 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to R. C. Cooper
Address Box 751,
Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
James Porter (employee of owner) or (owner/operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature) James Porter

(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January 1951

My commission expires 3-17-1951

W. D. Smith
Notary Public.

PLUGGING
FILE SEC 26 T 9 R 22W
BOOK PAGE 55 LINE 6
9-48-10M

WELL RECORD

15-065-02258-00-00

Company Citizen Service Oil Co. Well No. 2 Farm Barber "B"
 Location 990' South and 990' West of N/4 Corner Sec. 26 T. 9 R. 23W
 Elevation 2353 (2350 Gr.) County Osage State Kansas
 Drlg. Comm. December 31, 1950 Contractor R. W. Rine Drilling Company
 Drlg. Comp. January 12, 1951 Acid None
 T. D. 3963' Initial Prod. None - Dry Hole; P. & A. 1-12-51

CASING RECORD:
 8-5/8" @ 240' con. 175 sticks cement

FORMATION RECORD:

surface clay	0-40
shale & shells	240
shale, shells & sand	1490
anhydrite	1655
shale & shells	1870
shale, shells & lime	2665
lime & shale	3430
lime	3725
lime & shale	3850
lime, shale & chert	3898
lime	3903
lime & chert	3963 T. D.

Top Hedge	3542'
Top Lansing	3559'
Top Cherty Conglomerate	3852'
Top Arbuckle	3877'
Penetration	66'
Total Depth	3963'

INFO:	500'	00
	1000'	100
	1500'	200
	2000'	300
	2500'	400
	3000'	500

7-7/8" rotary hole.

Drill stem test 3890-3902, rec. 25'
 rotary mud, no oil, 30 mins., RHP 434.

Drill stem test 3638-53, rec. 60'
 watery mud, few specks of oil, 30
 mins., RHP 1142.

Drill stem test 3899-3903, rec. 170'
 water slightly specked with dead oil,
 30 mins., 1230 RHP.

26-9-22W
 55-6

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 30 1951
 GEOL. DIVISION
 Topeka, Kansas

