

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-02942-00

LEASE NAME Holzhauser

WELL NUMBER #1-B (401)

SPOT LOCATION NW NW NE

SEC. 26 TWP. 9 RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed 7-18-70

Plugging Commenced 4-19-84

Plugging Completed 4-19-84

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Collins & Collins Oil Company

ADDRESS 1007 Cody - Suite A, Hays, Kansas 67601

PHONE # (913) 628-1046 OPERATORS LICENSE NO. 8722

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? ? If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3820'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	237'	-0-
				5 1/2"	3820'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

filled hole with cement as per attached Allied invoice

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor John B. Collins License No. 5465

Address 1007 Cody - Suite A, Hays, Kansas 67601

STATE OF Kansas COUNTY OF Ellis, ss.


John B. Collins

(operator) of above-described well, being first duly sworn on oath, says: I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John B. Collins

(Address) 1007 Cody - Suite A, Hays, KS

SUBSCRIBED AND SWORN TO before me this 7th day of May, 1984



Gloria J. Brown
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
5/15/84
MAY 15 1984

CONSERVATION DIVISION
Wichita, Kansas

My Commission expires _____
My Appt. Expires _____

Company Cities Service Oil Co. Well No. 1 Farm Holshauer WSP
 Location 330' South and 330' East of N/4 Cor. Sec. 26 T. 9 R. 22W
 Elevation 2368 (2366 Gr.) County Graham State KANSAS
 Drig. Comm. October 7, 1950 Contractor R. W. Rine Drilling Company
 Drig. Comp. October 16, 1950 Acid 1500 gals. 10-24-50
 T. D. 3820' Initial Prod. Physical Potential: 143 oil, 3% water, 24 hrs: (10-26-50)
 P. D. 3796'

CASING RECORD:

8-5/8" @ 237' con. 175 sx cement
 5-1/2" @ 3820' con. 175 sx cement, and
 from 1877' to surface
 with 550 sacks

FORMATION RECORD:

surface clay & lime	237
shale, shells, sand	1830
anhydrite	1835
shale & shells	2190
shale, shells & lime	2715
lime & shale	3320
lime	3695
lime & shale	3820

3820 RSD = 3820 SIM

Drill stem test 3614-32, rec. 30'
 oil and mud, 180' oil in 30 mins.,
 S.H.P. 760%; flow pressure 80%.

Topoke	3372'
Reebner	3515'
Dodge	3563'
landing	3591'-12/16
Base Kansas City	3806'
Total Depth	3820'

Drilled cement to 3796 SIM.
 -1253-64
 Perf. 41 shots 3621-32

933' oil and 3 gals. water in 15 hrs.
 Add: Perfs: 9-5-56
 29 shots 3754-61
 33 shots 3709-47-1
 25 shots 3718-24

SYNO: 500' 1°
 1000' 1°
 1500' 1°
 2000' 1°
 2500' 1°

7-7/8" rotary hole.

Jan 1953 40 oil - 10 parts - 24 hrs.
 9-11-56 52 oil 26 wtr. 24 hrs.

15-065-02942-00-00

EXHIBIT B

CASING INFORMATION

CITIES SERVICE OIL CO.

IRONCLAD UNIT, GRAHAM COUNTY, KANS.

<u>Size</u>	<u>Length</u>	<u>Seat Depth</u>	<u>Condition</u>	<u>Cemented or Mudded</u>	<u>Est. Ft. Encased in Cement</u>	<u>Sacks Cement Used</u>
8 5/8"	237'	237'	Good	Cemented	237'	175
5 1/2"	3820'	3820'	Good	Cemented	700'	175

D.V. Tool @ 1877' cemented with 550 sacks