

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-21594 -00-00

LEASE NAME Holzhauser South

WELL NUMBER Ironclad #410

2,970 Ft. from S Section Line

1,650 Ft. from E Section Line

SEC. 26 TWP. 9S RGE. 22 (E) or (W)

COUNTY Graham

Date Well Completed _____

Plugging Commenced 3/15/00

Plugging Completed 3/15/00

APR 17 2000
4/17/00

CONSERVATION DIVISION

Wichita, Kansas

LEASE OPERATOR Starr F. Schlobohm

ADDRESS 47 Michawanic Rod., Sanbornville, NH 03872-3787

PHONE# (603) 522-9760 OPERATORS LICENSE NO. 4952

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 15, 2000 (date)

by Herb Dienes, Hays, KS KCC Office (KCC District Agent's Name).

Is ACO-1 filed? Don't know If not, is well log attached? No, not available

Producing Formation Lansing/KC Depth to Top 3,590' Bottom 3,828' T.D. 3,830'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From Surface	To	Size	Put in	Pulled out
		Surface	177'	8 5/8"	177'	None
		Surface	3828	5 1/2"	3,828'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. See attached Allfield Cementing Co., Inc. bill and work ticket attached.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Starr F. Schlobohm

STATE OF New Hampshire COUNTY OF Carroll, ss.

Starr F. Schlobohm (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Starr F. Schlobohm

(Address) 47 Michawanic Rd, Sanbornville, NH 03872

SUBSCRIBED AND SWORN TO before me this 13th day of April 19 2000

JoAnne M. MacDonald Notary Public
My Commission Expires: NOTARY PUBLIC OF NEW HAMPSHIRE
My Commission Expires Sept. 15, 2002

ALLIED CEMENTING CO., INC.

1364

Federal Tax: [REDACTED]

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>3-15-00</u>	SEC. <u>26</u>	TWP. <u>9S</u>	RANGE <u>22W</u>	CALLED OUT	ON LOCATION <u>9:30 AM</u>	JOB START <u>10:30 AM</u>	JOB FINISH <u>12:30 PM</u>
LEASE <u>FRONCIAN</u>	WELL # <u>4-10</u>	LOCATION <u>WAKEENCY 14N-7E-3/4N</u>			COUNTY <u>GRAHAM</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR <u>CO Tools</u>	OWNER <u>SAME</u>
TYPE OF JOB <u>OLD HOLS</u>	
HOLE SIZE _____ T.D. _____	
CASING SIZE <u>5 1/2"</u>	DEPTH _____
TUBING SIZE <u>2"</u>	DEPTH <u>3100'</u>
DRILL PIPE _____	DEPTH _____
TOOL _____	DEPTH _____
PRES. MAX _____	MINIMUM _____
MEAS. LINE _____	SHOE JOINT _____
CEMENT LEFT IN CSG. _____	
PERFS. _____	
DISPLACEMENT _____	

CEMENT	AMOUNT ORDERED <u>325 SKS 60/40 POZ 10% 6CL</u>
	<u>800 # HULLS</u>
	<u>USED 260 SKS 60/40 POZ 10% 6CL + 800 # HULLS</u>
COMMON	<u>156 SKS @ 6.35 = 990.60</u>
POZMIX	<u>104 SKS @ 3.25 = 338.00</u>
GEL	<u>22 SKS @ 9.50 = 209.00</u>
CHLORIDE	_____ @ _____ = _____
<u>HULLS</u>	<u>8 SKS @ 15.50 = 124.00</u>
	_____ @ _____ = _____
	_____ @ _____ = _____
	_____ @ _____ = _____
	_____ @ _____ = _____
HANDLING	<u>325 SKS @ 1.05 = 341.25</u>
MILEAGE	<u>4¢ per sk/mile = 715.00</u>

EQUIPMENT

PUMP TRUCK # <u>300</u>	CEMENTER <u>TERRY</u>
	HELPER <u>WAYNE</u>
BULK TRUCK # <u>280</u>	DRIVER <u>ANDREW</u>
BULK TRUCK # _____	DRIVER _____

TOTAL 2,717.85

REMARKS:

MIX 75SKS CEMENT WITH 300# HULLS
DOWN TUBING AT 3100'.
MIX 75SKS CEMENT WITH 300# HULLS
AT 2000' DOWN TUBING.
MIX 65SKS CEMENT + CIRCULATE TO SURFACE
AT 900' DOWN TUBING, HOOK ON CASING WITH
5/8 SWEDGE MIX 45SKS. PRESSURED TO 300 PSI.
SHUT IN AT 200 PSI, TEST BACKSIDE TO 500 PSI.
THANK YOU

SERVICE

DEPTH OF JOB	<u>3100'</u>
PUMP TRUCK CHARGE	<u>450.00</u>
EXTRA FOOTAGE	_____ @ _____ = _____
MILEAGE	<u>55 miles @ 3.00 = 165.00</u>
PLUG	_____ @ _____ = _____
	_____ @ _____ = _____
	_____ @ _____ = _____

TOTAL 615.00

CHARGE TO: SCHLOBOHM STARR F. OIL OPERATION

STREET _____
CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@ _____ = _____
_____	@ _____ = _____
_____	@ _____ = _____
_____	@ _____ = _____
_____	@ _____ = _____

TOTAL _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE John P. [Signature]

TAX _____
TOTAL CHARGE _____
DISCOUNT _____ IF PAID IN 30 DAYS

PRINTED NAME _____

ALLIED CEMENTING CO., INC.

P.O. BOX 31
 RUSSELL, KS 67665
 PH (785) 483-3887
 FAX (785) 483-5566

Invoice Number: 000000

Invoice Date: 02/11/00

Sold Stair F. Schlobonn
 To: 47 Michigan St. #30
 Overland Park, KS

[Redacted area]

Common	156.00	SKS	6.3500	990.60	T
Concrete	104.00	SKS	3.2500	139.00	T
Iron	22.00	SKS	0.7000	209.00	T
Steel	8.00	SKS	16.5000	124.00	T
Reinforcing	328.00	SKS	1.0500	341.25	T
High Rise* (see note)	55.00	MILE	13.0000	315.00	T
*10 SKS @ 0.05 per sk per ni					
Oil	1.00	JOB	450.0000	450.00	T
Mileage pay 1/2	55.00	MILE	3.0000	165.00	T

All Prices are to be Payable 30 Days Following
 Date of Invoice. 1 1/2% Charged Thereafter
 If Account CURRENT take Discount of \$ 3122.43
 COPY of paid within 30 days from Invoice Date

Subtotal: 3301.85
 Tax: 190.54
 Payments: 0.00
 Total: 3529.39