

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-065-00903-00-01

API NUMBER NA

LEASE NAME Moore

WELL NUMBER #1

330 Ft. from S Section Line

330 Ft. from E Section Line NW/4

SEC. 27 TWP. 9 RGE. 22 (or) (W)

COUNTY Graham

Date Well Completed 10/19/92

Plugging Commenced 11/27/90

Plugging Completed 11/27/90

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Clute Oil Corporation

ADDRESS 444 17th St, Suite 608

PHONE#(303) 623-6779 OPERATORS LICENSE NO. 30160

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 25, 1990 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? NA

Producing Formation F. Scott, L-KC Depth to Top 3654 Bottom 3922 T.D. 4020

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				<u>5 7/8</u>	<u>238</u>	<u>Ø</u>
				<u>5 1/2</u>	<u>3990</u>	<u>Ø</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

See attached

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor C+L Well Service License No.

Address P.O. Box 102 Plainville, KS 67063

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Clute Oil Corporation

STATE OF Colorado COUNTY OF Douglas, ss.

Clute Oil Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 444 17th St, Suite 608, CO 80202

SUBSCRIBED AND SWORN TO before me this 9th day of January, 19 91

[Signature]
Notary Public

My Commission Expires: 12-31-92

H & C OIL OPERATING, INC.

P. O. Box 86

PLAINVILLE, KANSAS 67663

November 28, 1990

MOORE #1
PLUGGING REPORT
CLUTE OIL CORPORATION

11-27-90 Move in and rig up C & L Well Service. Great Guns perforated one hole at 1885'. Tallied and ran 1970' of 2 3/8" tubing. Mixed 100 sacks cement, pumped down tubing. Pulled tubing to 1000' and mixed 30 sacks cement down tubing. Cement circulated to surface. Pulled tubing and pumped 10 sacks down 5 1/2" casing. Pressured up to 400#. Total cement in 5 1/2" = 140 sacks. Mixed and pumped 160 sacks cement and 200# of hulls down 8 5/8". All cement was 65/35 poz mix with 8% gel. Cemented by Allied Cementing. State plugger on location was Carl Goodrow.

RECEIVED
REGISTRATION COMMISSION

IAN 11 1991

REGISTRATION COMMISSION
PLAINVILLE, KANSAS