

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Graham

County. Sec. 27 Twp. 9 Rge. 22 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE

Lease Owner Victor Drilling, Inc.

Lease Name Sandlin Well No. 1

Office Address 301 Koch Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed 8-19 19 52

Application for plugging filed 8-19 19 52

Application for plugging approved 8-19 19 52

Plugging commenced 8-19 19 52

Plugging completed 8-19 19 52

Reason for abandonment of well or producing formation no commercial shows

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4042 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	183	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with heavy rotary mud from 4042 total depth to 175 feet; rock bridge and cement with 15 sx cement. Top plug at 40 feet with 10 sx cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Victor Drilling, Inc.

Address 301 Koch Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Victor F. Reiserer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God:

(Signature) Victor F. Reiserer
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 21st day of August, 19 52

My commission expires July 16, 1955

Alma E. Ross Notary Public.

PLUGGING
FILE SEC 27 T 9 R 22
BOOK PAGE 39 LINE 8

9/4/52

Victor Drilling, Inc.

No. 1 Sandlin

Sec 27-9S-22W
Graham County

Spud: 8-7-52
Comp: 8-19-52

Elev. 2381 KB
2379 DF
2376 Gr

183' 8 5/8" 125 sx

clay and sand	0-40
sand and clay	75
water sand	90
sand and shale	150
shale	1183
shale	659
brown sand	690
shale	700
shale and shells	1250
shale and shells	1783
shale	1850
anhydrite	1905
shale red bed	1965
shale and red bed	2215
shale and shells	2375
shale and lime	2760
shale and lime	3110
shale and lime	3354
shale	3454
shale and lime	3630
lime	3760
lime	3833
lime and shale	3952
lime and shale	3991
Arbuckle dolomite	4042
Total depth	4042

FORMATION TOPS	(SCHLUM)
Heebner	3576
Toronto	3600
Lansing	3617
Cherty Conglomerate	3992
Arbuckle	3996

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

I, Victor F. Reiserer, swear that to the best of my knowledge the foregoing is true.

Victor F. Reiserer
Victor F. Reiserer

Subscribed and sworn to before me this 21st day of August, 1952.

Alma E. Ross
Notary Public

My commission expires July 16, 1955.

PLUGGING
FILE SEC 27 T 9 R 22W
PAGE 39 LINE 8