

15-163-00020-00-00

LOG RECORD
E. C. GANOUNG NO. 1

LOCATION:

330' North of South Line and 330' West of
East Line of the SW/4 of Sec. 20-98-17W
Rooks County, Kansas

CONTRACTOR: B & H Drilling Co.
Drilling Comm: June 3rd, 1944
Drilling Comp: June 19th, 1944
Plugged & Abd: June 19th, 1944

INITIAL PRODUCTION:


COMPLETED FOR A DRY HOLE AT A TOTAL DEPTH OF 3698'

CASING RECORD:

10 3/4" OD 32.75# Rep. E.W. Casing set at 124' DF - Cemented with 90 Sacks of Dewey Const.
Cement mixed with 100# Calcium Chloride

FORMATION RECORD:

Sub Soil	0	2	Shale & Lime	2650	2908
Sandy Shale	2	70	Lime	2908	2945
Shale	70	135	Lime & Shale	2945	3085
Shale & Shells	135	530	Lime	3085	3128
Sand	530	583	Lime & Shale	3128	3217
Shale	583	660	Lime	3217	3305
Sand	660	730	Lime & Shale	3305	3345
Shale	730	740	Lime	3345	3425
Py. Iron	740	742	Lime - Cherty	3425	3455
Shale & Shells	742	925	Lime & Shale	3455	3560
Sand & Shells & Pyrites	925	1108	Cherty Cong.	3560	3612
Red Bed & Shells	1108	1225	Pyrites & Sand	3612	3616
Red Rock & Lime Shells	1225	1398	Sandy Shale	3616	3627
Red Bed	1398	1400	Shale	3627	3650
Anhydrite - Hard	1400	1437	Lime	3650	3674
Blue Shale & Shells	1437	1455	Lime & Chert	3674	3685
Shale & Shells	1455	1935	Lime, Chert & Pyrite	3685	3698 TD
Lime	1935	1980			
Shale & Lime	1980	2550			
Shale & Shells	2550	2625			
Lime, Pyrites & Shale	2625	2646			
Shale & Lime	2646	2650			



I, V. A. Knight, being first duly sworn, on oath state that I have knowledge of the facts and matter herein set forth and that the same are true and correct.

V. A. Knight
Dist. Supt.

Sworn and subscribed to before me this 22nd day of June 1944

[Signature]
Notary Public

My Commission expires Dec. 15th, 1944