


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 28 Twp 9S Rge. (E) 17 (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$
Lease Owner Barnett Drilling, Inc.
Lease Name Benedick Well No. 1
Office Address First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 9, 1951
Application for plugging filed March 9, 1951
Application for plugging approved March 9, 1951
Plugging commenced March 9, 1951
Plugging completed March 9, 1951
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - - - - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3,659 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Surface Casing				8 5/8"	161	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from 3,659 feet to 163 feet. Set wooden plug at 163 feet and filled surface casing with 15 sacks of cement to 117 feet. Filled surface casing with heavy mud from 117 feet to 45 feet. Set wooden plug at 45 feet and filled surface casing with 10 sacks of cement to bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1951 03-23-1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Barnett Drilling, Inc.
Address 117 First National Bank Building
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. R. Hunter (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) *W. R. Hunter*
First National Bank Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of March, 1951

My commission expires May 13, 1951
Adelaide Olivier
Notary Public.

28-5091-s 8-50-10M
PLUGGING
FILE SEC 28 T 9 R 17 W
BOOK PAGE 66 LINE 35

15-163-00346-00-00

BARNETT DRILLING, INC., ET AL

LOG OF BENEDICK WELL NO. 1

SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ SECTION 28-9S-17W, ROOKS COUNTY, KANSAS.

COMMENCED: February 21, 1951

COMPLETED: March 9, 1951

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface Clay	-0-	15
Sand	15	25
Shale	25	100
Shale and Shells	100	164
Shale	164	530
Shale and Shells	530	950
Sand	950	1090
Shale and Shells	1090	1400
Anhydrite	1400	1435
Shale and Shells	1435	1904
Shale and Lime	1904	1995
Lime	1995	2245
Lime and Shale	2245	2895
Lime	2895	3380
Lime and Shale	3380	3410
Lime	3410	3500
Lime and Shale	3500	3535
Lime	3535	3545
Conglomerate	3545	3631
Dolomite	3631	3659
Total Depth		3659

Set 8 5/8" 24# Surface Casing at 164 feet;
Cemented With 125 Sacks of Cement.

Dry and Abandoned.

CERTIFICATE

I, W. R. Hunter, Vice-President of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief the above is a true and correct log of the Benedick Well No. 1, located in the SE $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ of Section 28-9S-17W, Rooks County, Kansas.

W. R. Hunter

Subscribed and sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, this 20th day of March, 1951.

Delaine Oliver
Notary Public.

My commission expires May 12, 1951.

