

15-163-30131-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 35 Twp. 9S Rge. (E) 17(W)
Location as "NE/CNW/SW" or footage from lines SW NW SE
Lease Owner Pickrell Drilling Company
Lease Name Westhusin Estate Well No. 1
Office Address 705 4th Natl Bank Bldg, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 22, 19 65
Application for plugging filed September 22, 19 65
Application for plugging approved September 22, 19 65
Plugging commenced September 22, 19 65
Plugging completed September 22, 19 65
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	197'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 550', set plug, cemented with
25 sacks cement. Heavy mud to 185', set
plug, cemented with 18 sacks. Heavy mud
to 40', set plug. Cemented with 10 sacks
to bottom of cellar. Plugged rat hole with
2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1965
10-4-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pickrell Drilling Company
Address 705 4th Natl Bank Bldg, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebits (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th Natl Bank Bldg, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN to before me this 29th day of September, 19 65

My commission expires June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 Fourth Natl Bank Bldg
Wichita, Kansas 67202

Rotary Drilling Commenced 9-14-65
Rotary Drilling Completed 9-22-65

LOCATION: WESTHUSIN ESTATE No. 1, SW NW SE Section 35-9S-17W, Rooks:County, Kansas

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (9 jts) 8 5/8" surface casing set at 197' cemented with 125 sacks cement. Circulated. Completed 4:30 P.M. September 14, 1965. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

125	Post Rock & Clay	<u>C. F. S.</u>
195	Blue Shale	3161
197	Cement	3183
700	Shale	3250
985	Sand & Shale	3291
2020	Shale & Shells	3300
2120	Shale, Shells & Lime	3315
3133	Lime & Shale	3347
3240	Lime	3360
3298	Lime & Shale	3400
3360	Lime	3445
3366	Lime & Shale	3510
3475	Lime	3550
3510	Sandy Lime & Shale	3580
3590	Lime & Shale	3605
3640	Lime - RTD	3606
		3610
		3640

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1965
CONSTRUCTION DIVISION
Wichita, Kansas

Slope Tests
2000
2500
3000
3500

S. L. M.
2750
3037
3366

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 29th day of September, 19 65, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
Maxine Blackman, Notary Public