


15-163 - 00351-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 36 Twp. 9 Rge. 17 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW SE
Lease Owner E. J. Doley
Lease Name Overholser Well No. 1
Office Address Hays, Ks.
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 1-10-51 19
Application for plugging filed 1-10-51 19
Application for plugging approved 1-10-51 19
Plugging commenced 1-10-51 19
Plugging completed 1-10-51 19
Reason for abandonment of well or producing formation



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3640 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud to 133'. Set plug and spotted 15 sacks cement.

Filled pipe with mud to 30'. Set plug and spotted 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to E. J. Doley
Address Hays, Ks.

STATE 04-03-1951
APR 3 1951
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF Kansas, COUNTY OF Sedgwick, ss.
W. R. Murfin (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W.R. Murfin
910 Union Natl. Bank Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1951

Genevieve Hays
Notary Public.

My commission expires 3-5-52

PLUGGING
FILE SEC. 36 T. 9 R. 17 W
BOOK PAGE 55 LINE 18

15-163-00351-00-00

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY E. J. Doley

SEC. 36 T. 9 R. 17W

FARM Overholser

NO. 1

LOC. SW SW SE

TOTAL DEPTH 3640
COMM. 12-30-50

COMP. 1-10-51


COUNTY Rooks

KANSAS

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED



CASING

20 10
15 8 135
12 6
13 5

ELEVATION

PRODUCTION Dry

FIGURES INDICATE BOTTOM OF FORMATIONS

60 shale
65 sand
480 shale, blue
550 gray shale & shells
580 sand & shale
670 shale & shells
780 gray shale & sand
820 black shale & shells
950 blue shale & shells
1020 shale & sand
1305 red bed & shale
1305 red bed & shale
1345 Anhydrite
1715 shale & shellz
1880 salt & shale
1900 shale & shells
1965 brkn. lime
2080 lime
2125 brkn. lime
2185 lime
2240 lime & shale
2320 lime
2375 brkn. lime
2430 shale & lime
2530 shale & lime shells
2978 shale & lime
3120 lime
3140 lime & shale
3375 lime
3380 shale
3400 cherty lime
3500 lime
3565 lime & shale
3606 cong.
3640 Arb.

Tops

Anhydrite 1305 (plus 774)
Heebner 3200 (-1121)
Lansing 3240 (-1161)
B.K.C. 3488 (-1409)
Cong. 3537 (-1458)
Simpson Sh. 3568 (-1489)
Simpson Dolo. 3580 (-1501)
Arbuckle 3606 (-1527)

No shows

STATE OF KANSAS)
) SS:
SEDGWICK COUNTY)

I. W. R. Murfin, of the Murfin Drilling Co., upon oath state that the above is a true and correct copy of the log of the No. 1 Overholser well.

W. R. Murfin
W. R. Murfin

Subscribed and sworn to before me this 16th day of January, 1952.

Genevieve Hoop
Notary Public

My Commission Expires: 3-5-52

