

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,282-00-00

LEASE NAME WESTHUSIN B

WELL NUMBER 1-B^{KCC}_{ZAP}

990 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 36 TWP. 9S RGE. 17 ~~XX~~ or (W)

COUNTY Rooks

Date Well Completed 1/11/70

Plugging Commenced 8/8/86

Plugging Completed 8/8/86

LEASE OPERATOR Leben Oil Corporation

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6566

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS

Is ACO-1 filed? on old form if not, is well log attached? ---

Producing Formation Toronto, LKC, & Marmaton Depth to Top 3161 Bottom 3436 T.D. 3568

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3161	67	8-5/8	209	-0-
LKC	Oil	3205	3358	5-1/2	3567	1430
Marmaton	Oil	3432	36			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set bottom hole plug w/sand + 5 SXS cement to 3100'. Cut off 5-1/2" @ 1430'.
Pumped 200 SXS thrifty-mix + 6 SXS hulls from 2000'-SURF.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg

(Address) C. Van Valkenburg
P.O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 86

Carol Sue Brungardt
Notary Public

My Commission Expires: 2/11/89


SUC 21
08-21-1986

Geology

15-163-20282-00-00

WELL LOG

Company Leben Drilling, Inc.	Sec. 36 T. 9S R. 17W
Contractor Leben Drilling, Inc.	Loc. NW SW SW
Farm Westhusin "B" #1 1-B ^{KCC} _{2AP}	County Rooks
Total Depth 3568'	Casing 8 5/8" 20# N.C. 209' w/165 Common 2% C.C.
Commenced 1-4-70	Production Prod.
Completed 1-11-70	




Figures Indicate Bottom of Formations

20	Clay & Post Rock
209	Shale & Sand
750	Shale
970	Sand
1265	Red Bed
1302	Anhydrite
1550	Red Bed & Shale
1785	Shale
2455	Shale & Lime
2625	Lime
2929	Lime & Shale
3568	Lime
<u>3568</u>	<u>RTD</u>

State of Kansas)
 County of Barton) SS

I, James R. Rodgers of the Leben Drilling, Inc.
 upon oath state that the above and foregoing is a true and correct copy
 of the log of the Westhusin "B" #1 Well.



James R. Rodgers

Subscribed and sworn to before me this 6th day of February, 1970

My Commission Expires:
 November 13, 1973

Helen L. Lindemuth

JUL 30 1986