

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-20,283
LEASE NAME WESTHUSIN ^{CO-00}
WELL NUMBER 2-B ^{KCC} _{ZAP}
330 Ft. from S Section Line
4290 Ft. from E Section Line
SEC. 36 TWP. 9S RGE. 17 ~~(E)~~ or (W)
COUNTY Rooks
Date Well Completed 1/19/70
Plugging Commenced 8/8/86
Plugging Completed 8/8/86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Leben Oil Corporation
ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468
PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6566
Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes
Which KCC/KDHE Joint Office did you notify? District 6, Hays, KS
Is ACO-1 filed? on old form if not, is well log attached? ---
Producing Formation Toronto, LKC, & Marmaton Depth to Top 3174 Bottom 3444 T.D. 3580
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto	Oil	3174	77	8-5/8	209	-0-
LKC	Oil	3231	3360	5-1/2	3579	1440
Marmaton	Oil	3440	44			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Set bottom hole plug w/sand + 5 SXS cement to 3120'. Cut-off 5-1/2" @ 1440'.
POOH & LD. Pumped 200 SXS thrifty-mix + 6 SXS hulls from 2000'-SURF.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568
Address P. O. Box 21468, Tulsa, OK 74121-1468
STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Van Valkenburg
(Address) P.O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 18th day of August, 19 86

Carol Sue Brungardt
Notary Public

My Commission Expires: 2/11/89

AUG 21 1986
08-21-1986

15-163-20283-00-00

Geology

WELL LOG

Company Leben Drilling, Inc.

Sec. 36 T. 9S R. 17W

Contractor Leben Drilling, Inc.

Loc. SE SW SW

Farm Westhusin "B" #2 2-B¹⁶⁵ ZAP

County Rooks


Total Depth 3580'

Casing 8 5/8" 20# N.C. set' @ 209'
w/165 sks. Common 2% C.C.

Commenced 1-12-70

Production Prod.

Completed 1-19-70



Figures Indicate Bottom of Formations

150	Clay, Post Rock
209	Blue Shale
810	Shale & Sand
960	Sand
1261	Red Bed
1295	Anhydrite
1750	Shale
2970	Lime & Shale
3530	Lime
3580	Lime & Shale
<u>3580</u>	<u>RTD</u>

State of Kansas

County of Barton

SS


I, James R. Rodgers of the Leben Drilling, Inc.
upon oath state that the above and foregoing is a true and correct copy
of the log of the Westhusin "B" #2 Well.

James R. Rodgers

Subscribed and sworn to before me this 6th day of February, 1970

My Commission Expires:
November 13, 1973

Helen L. Lindemann **EIVED**
NOTARY COMMISSION
KANSAS



JUL 30 1986