

15-163-02380-00-00  
**WELL PLUGGING RECORD**


STATE OF KANSAS  
 STATE CORPORATION COMMISSION

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 800 Bitting Building  
 Wichita, Kansas

OR  
**FORMATION PLUGGING RECORD**

Strike out upper line  
 when reporting plug-  
 ging off formations.

NORTH



Locate well correctly on above  
 Section Plat

ROOKS County. Sec. 35 Twp. 9S Rge. 18 (E) (W)  
 Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SW 1/4 SW 1/4 SW 1/4  
 Lease Owner The Aylward Production Company  
 Lease Name YEAGY Well No. 1  
 Office Address 813 First National Bank Bldg. Wichita, 2, Kansas.  
 Character of Well (completed as Oil, Gas or Dry Hole) DRY  
 Date well completed May 5, 1947  
 Application for plugging filed May 6, 1947  
 Application for plugging approved  
 Plugging commenced May 5, 1947  
 Plugging completed May 5, 1947  
 Reason for abandonment of well or producing formation  
 If a producing well is abandoned, date of last production = 19  
 Was permission obtained from the Conservation Division or its agents before plugging was com-  
 menced? Yes

Name of Conservation Agent who supervised plugging of this well  
 Producing formation Depth to top Bottom Total Depth of Well 3711 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	260'	None
				13-3/8"	44'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed wood plug to 270' with rotary pipe, put rock bridge on top of wood plug. Mixed 18 sacks cement on floor, put down to rock bridge through surface pipe, pipe was dry, placed cement sack in hole, pumped rotary mud between lower and top plug; top plug started at 40', bridged to hold Kelley at 35', filled to surface with cement. 8-5/8" pipe cut off at top of 13-3/8" pipe with torch.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Aylward Production Company  
 Address 813 First National Bank Bldg., Wichita, 2, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
 N. W. AYLWARD (employee of owner) or (owner or operator) of the above-described well,  
 being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) N. W. Aylward  
 410 E. 4th St. Hutchinson Kansas  
 (Address)

SUBSCRIBED AND SWORN to before me this 9th day of May 1947  
 Notary Public.  
 5-10-47

My commission expires February 25, 1950.

**PLUGGING**  
 FILE SEC 35 T 9 R 18W  
 BOOK PAGE 108 LINE 44

15-163-02380-00-00

YEAGY NO. 1

Casing Records:

13 3/8 - 44'

8 5/8 - 270'

Company: The Aylward Production Company  
Contractor: Aylward Drilling Company

Commenced: April 20, 1947  
Completed: May 5, 1947

Location:

SW<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub> SW<sup>1</sup>/<sub>4</sub> of Sec.  
35-9-18W, Rooks County,  
Kansas.

Elevation: 2120'

Potential: Dry

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface	0	2	
Clay	2	15	
Clay Sandy	15	25	
Sand	25	35	Set 13 3/8" @ 44'
Shale Brown	35	70	
Shale Gray	70	180	
Shale Blue	180	265	Set 8 5/8" @ 265' & cemented w/100 sz.
Shale & Shells	265	710	
Sand	710	805	
Sand & Shale	805	965	
Shale & Shells	965	995	
Sand	995	1025	
Sand & Shale	1025	1200	
Red Bed & Shale	1200	1350	
Anhydrite	1350	1370	
Red Bed & Shale Shells	1370	1450	
Shale	1450	1695	
Shale Shells	1695	2000	
Shale & Shells	2000	2140	
Shale	2140	2240	
Lime & Shale	2240	2270	
Lime, Sandy	2270	2426	
Shale & Shells	2426	2645	
Lime	2645	2655	
Shale	2655	2680	
Lime	2680	2790	
Shale & Lime	2790	3335	
Lime	3335	3560	
Pyrite of Iron	3560	3561	
Lime & Conglomerate	3561	3592	
Lime & Chert	3592	3642	
Lime & Conglomerate	3642	3712	

GEOLOGICAL TOPS

Lansing	3312'
Very Small Show of Oil	3503-3505'
Base K. C.	3559'
Conglomerate	3582'
Arbuckle	3668'
Total Depth	3712'

3712 T. D.

S-10-47

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*[Signature]*

Subscribed and Sworn to before me this 9th day of May, 1947

*[Signature]*

My commission expires February 25, 1950.



PLUGGING  
 FILE NO. 35-9-18W  
 BOOK 108 44



15-163-02380-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
800 BITTING BUILDING  
WICHITA, KANSAS  
May 8, 1947

IN REPLY PLEASE  
REFER TO THIS  
SUBJECT

Aylward Production Co.  
813 1st Nat'l Bank Bldg.  
Wichita, Kansas

Gentlemen:

IN ACCOUNT WITH Conservation Division, State Corporation Commission  
Wichita, Kansas

WE Charge YOU

Plugging Assessment.....\$ 25.00

Well No. 1  
Farm Yeagy  
Description SW SW SW 35-9-18W  
County Hooks  
File: 108-44

The assessment for the plugging of all wells in the State of Kansas is one cent per foot, with a maximum of \$25.00 and a minimum of \$5.00.

This assessment will be past due June 6, 1947

PLEASE RETURN ONE COPY WITH REMITTANCE

NOTE: We also need a Well Log and Well Plugging Record on this well to complete our files.

MAY 13 1947

*Handwritten:* Paid 5/13/47  
*Signature:* [unclear]

DETACH VOUCHER BEFORE DEPOSITING  
IF INCORRECT RETURN AT ONCE

ENDORSEMENT IS RECEIPT IN FULL

CHECK

NO.

1379

DATE

DESCRIPTION

AMOUNT

5-9-47

Vo-4-128

Per attached statement

\$ 25.00

THE AYLWARD PRODUCTION CO.  
WICHITA, KANSAS